



X-Flat Ties Heavy Duty

Description:

OCM, Inc's X-Flat Ties are to be used in most steel ply modular forming systems utilizing wedge bolts to secure form work.

Features:

- Safe working load: 3,500 lbs.
- Available in 7 sizes.

Additional Notes: SWL provides a safety factor of approximately 2 to 1.

Item Number	Safe Working Load (lbs)	Wall Size (in)	Filler Type
FT06HD	3,500	6	Heavy Duty
FT08HD	3,500	8	Heavy Duty
FT10HD	3,500	10	Heavy Duty
FT12HD	3,500	12	Heavy Duty
FT14HD	3,500	14	Heavy Duty
FT16HD	3,500	16	Heavy Duty
FT18HD	3,500	18	Heavy Duty