



X-Flat Ties

Description:

OCM, Inc's X-Flat Ties are to be used in most steel ply modular forming systems utilizing wedge bolts to secure form work.

Features:

- Available in 37 sizes.
- Safe working load: 3,000 lbs.

Additional Notes: SWL provides a safety factor of approximately 2 to 1.

Item Number	Safe Working Load (lbs)	Wall Size (in)	Filler Type
FT84SP	3,000	84"	Standard
FT42SP	3,000	42	Standard
FT44SP	3,000	44"	Standard
FT46SP	3,000	46"	Standard
FT48SP	3,000	48	Standard
FT54SP	3,000	54	Standard
FT60SP	3,000	60	Standard
FT66SP	3,000	66"	Standard
FT72SP	3,000	72"	Standard
FT78SP	3,000	78"	Standard
FT24SP	3,000	24	Standard
FT40SP	3,000	40	Standard
FT38SP	3,000	38"	Standard
FT36SP	3,000	36	Standard
FT34SP	3,000	34	Standard
FT32SP	3,000	32	Standard
FT30SP	3,000	30	Standard
FT28SP	3,000	28	Standard
FT26SP	3,000	26	Standard

Item Number	Safe Working Load (lbs)	Wall Size (in)	Filler Type
FT23SP	3,000	23"	Standard
FT13SP	3,000	13"	Standard
FT14SP	3,000	14	Standard
FT15SP	3,000	15	Standard
FT16SP	3,000	16	Standard
FT17SP	3,000	17"	Standard
FT18SP	3,000	18	Standard
FT19SP	3,000	19	Standard
FT20SP	3,000	20	Standard
FT21SP	3,000	21"	Standard
FT22SP	3,000	22"	Standard
FT04SP	3,000	4	Standard
FT12SP	3,000	12	Standard
FT11SP	3,000	11	Standard
FT10SP	3,000	10	Standard
FT09SP	3,000	9	Standard
FT08SP	3,000	8	Standard
FT06SP	3,000	6	Standard