

SCLI50X3P



Straight coil loop inserts are used in a lot of precast applications like lifting walls.

Part Number	SCLI50X3P
Safe Working Load (lbs)	2,250
Dia. (in)	1/2"
Length (in)	3"