



Stabox

The OCM Stabox is a two piece system of pre-assembled rebar and box keyway unit. Box is made in two halves from plain steel or galvanized sheet metal per customer requirement. Typical dimensions of box are: 1.5" deep; 2.5", 3.5", 6" or 8" wide by 48" long. Those are standard sizes but product can be fabricated in almost any shape required. The two part box is designed so back portion of box remains, front portion removes allowing access to the bend out portion of rebar. The box itself and both ends are taped together. Simply nail box to form installation.

Features:

- Fast and easy to use.

Additional Notes: Please contact for more information.

Part Number	Stabox
-------------	--------